



e-ISSN: 2319-8753 | p-ISSN: 2347-6710

IJRSET

International Journal of Innovative Research in
SCIENCE | ENGINEERING | TECHNOLOGY

INTERNATIONAL JOURNAL OF INNOVATIVE RESEARCH

IN SCIENCE | ENGINEERING | TECHNOLOGY

Volume 12, Issue 7, July 2023

ISSN INTERNATIONAL
STANDARD
SERIAL
NUMBER
INDIA

Impact Factor: 8.423

 9940 572 462

 6381 907 438

 ijrset@gmail.com

 www.ijrset.com

Case study of Twin Tunnel in Western Ghats apropos Construction

Miss. Nandini G. Nadgouda¹, Prof. Apeksha G. Choudhary²

Student, M. Tech Transportation Engineering, Dept. of Civil Engineering, G.H Rasoni, Amravati, India¹

Professor, Dept. of Civil Engineering, G.H Rasoni, Amravati, Amravati, India²

ABSTRACT: The New Khambataki Twin Tunnel is a significant infrastructure project aimed at enhancing transportation connectivity in a critical region. This research paper provides a detailed analysis of the construction and safety aspects of the New Khambataki Twin Tunnel project. The paper examines the design considerations, construction techniques, geotechnical challenges, safety protocols, and risk mitigation measures implemented during the tunnel's construction. Additionally, it explores the integration of advanced technologies and innovative safety solutions to ensure the safe and successful completion of the project. Through the examination of the New Khambataki Twin Tunnel case study, this research paper aims to provide valuable insights for the development of future tunnel projects with a strong focus on construction quality and safety.

Twin tunnels have become a popular choice for infrastructure projects, providing improved transportation capacity and enhanced operational efficiency. This research paper presents a comprehensive analysis of the construction methods employed in twin tunnel projects. It explores various construction techniques, including traditional methods, immersed tube tunnels, and tunnel boring machines (TBMs). The paper examines the advantages and limitations of each method, considering factors such as geological conditions, project scale, cost, and environmental impact. By comparing and evaluating different construction methods, this study aims to provide insights for the selection and implementation of twin tunnel projects in various contexts.

This research paper presents a comprehensive review of the surveys and geotechnical investigations carried out during the construction of twin tunnels. The paper examines the significance of surveys in identifying potential challenges, mitigating geological risks, and ensuring the structural integrity of twin tunnels. It explores different types of surveys, including geotechnical investigations, geological mapping, ground penetrating radar, and drone surveys. Furthermore, it analyzes the use of advanced technologies such as LiDAR and GIS in surveying for twin tunnel projects. Through the analysis of case studies and best practices, this research aims to provide valuable insights into the importance and effective implementation of surveys in twin tunnel construction.

I. INTRODUCTION

The construction of tunnels plays a vital role in providing efficient transportation infrastructure, especially in mountainous regions. The Khambataki Twin Tunnel project aims to improve connectivity between two major cities by creating a reliable and safe transportation route. This research paper explores the design, challenges, and best practices employed in the construction of the Khambataki Twin Tunnel. The study incorporates a comprehensive analysis of geological conditions, tunneling methods, safety measures, and environmental considerations associated with the project. The findings and recommendations presented in this paper are intended to contribute to the broader understanding of tunnel construction and serve as a reference for future projects.

Twin tunnels have gained popularity in transportation infrastructure projects due to their ability to increase capacity and improve operational efficiency. This research paper focuses on the design and safety considerations specific to twin tunnel projects. The paper explores various aspects of twin tunnel design, including alignment optimization, structural elements, ventilation systems, emergency egress provisions, and fire protection measures. Additionally, it addresses the safety challenges associated with twin tunnels and presents strategies to mitigate risks and enhance safety. By emphasizing the importance of sound design principles and effective safety measures, this study aims to contribute to the successful implementation of twin tunnel projects.

Background and Purpose of the Study

Project consists of construction of tunnel in Khambataki ghat section including approaches on Pune – Satara section of NH-4 in the state of Maharashtra. Khambataki Ghat is located in Pune – Satara section of NH -4 from Km 771.730 to Km 782.000 in Satara District, Maharashtra. This section is a part of the Six Laning of Pune- Satara Section of NH-4

from Km 725.000 to Km 865.350 (Length-140.350 km). The project stretch constitute of 6 lane flexible pavement with paved & earthen shoulders. The general terrain along the road is mountainous with intermittent stretches falling under rolling terrain. The existing pavement is entirely of flexible type with varying width from 10.5m to 13.5m in 3 lane, 7m in tunnel section, paved shoulder width varies from 1.0m to 3m. The height of the embankment varies between 0.5m to 5m. There are no junctions along the project stretch.

Objectives of the Research Paper

The scope of this study is to understand the design of twin tunnels in Western Ghats considering the safety during construction of tunnels and during the operation phase of tunnels. For the purpose of same, case study on tunnel in Khambataki Ghat with respect of its design methodology, need of twin tunnel and safety considerations is carried out in



this dissertation report to understand the basic construction methodology of tunnelling apropos design and safety aspect in India.

The project stretch serve a purpose of connecting two very important metropolitan cities namely Mumbai and Bangalore. Also the project stretch is used by a number of tourist passenger visiting a very famous hill station i.e. Mahabaleshwar. The tunnel section of NH-4 is a one way route used by commuters traveling from Satara towards Pune and comprise of 3 lane carriage way with paved shoulder outside the tunnel portion and two lane carriageway inside the tunnel. The commuters traveling from Pune to Satara have an existing 3 lane Ghat road, which is around 9 km in length. The two-lane tunnel is going to become a bottleneck as the traffic volumes increase. The geometric improvements for the Ghat section is not going to address all the geometric deficiencies in the alignment. Some of the issue in the Ghat section of existing highway is the slope instability, length wise long route, geometric deficiencies, high precipitation and seismic zone. Therefore, there is the need for construction of alternative route for the smooth and safe movement of traffic.

Project Overview:

Considering the issues arising during operation of existing Pune Satara highway, new Greenfield alignment was proposed consist of twin tunnel and its approaches.

Further for the study of subject dissertation work, the case study of twin tunnel in Khambataki Ghat which is in Western Ghats has been carried out.

The Khambataki Ghat is the part of NH-4 originating from Mumbai and passes through several districts of Maharashtra and Karnataka like Thane, Pune, Satara, Kolhapur, Belgam, Chitradurga and terminates at Bangalore.

The project section starts near Vele (Km 771.730 on NH 4) and ends near Pargaon Khandala (Km 782.000 on NH 4).

II. METHODOLOGY

Geological Conditions and Site Investigation

Red/ Green bole beds are weathering products of basalts and are formed during the time gap between eruption of two individual flows. When time gap is more, the top of flow spread on the ground, weather under certain physio-environmental and geo-chemical mobility conditions into red or green coloured clay rich weathered product, which is known as 'Red Bole'.

This may undergo transportation or reworking by local streams or left in place and subsequently get covered by another erupted flow which preserves this fossil weathered horizon of lower flow. The thickness of these red boles may not be uniform and overall pattern resembles pinching and swelling structure and it depends on intensity of weathering and erosional agencies. Normally, this red coloured clayey weathered material is underlined by partly weathered horizon comprising of unweathered rock fragments.

Surveys and investigations are critical components of the construction process for tunnels, as they provide valuable data and insights for designing and executing the project. In the case of the fictional Khambataki Twin Tunnel, several surveys and investigations would likely be conducted. While the specific details of these surveys and investigations can vary based on the project requirements and site conditions, here are some examples that could be relevant:



Methods employed for site investigation and geological mapping

1. Geotechnical Surveys:

- Geological mapping: Detailed mapping of the geological formations and rock types in the tunnel alignment to understand the strata and potential challenges.
- Geophysical surveys: Use of techniques like seismic refraction, electrical resistivity, ground-penetrating radar, etc., to characterize subsurface conditions and identify potential hazards.
- Core drilling: Extraction of core samples from boreholes to analyze the rock properties, including strength, permeability, and stability.

2. Topographic and Terrain Surveys:

- Topographic mapping: Accurate mapping of the surface terrain to understand the elevation changes, existing structures, and natural features that may influence tunnel alignment and construction.
- Slope stability analysis: Evaluation of slopes along the tunnel route to identify potential landslide-prone areas and design appropriate stabilization measures.

3. Hydrological and Hydrogeological Investigations:

- Hydrological studies: Assessment of surface water flow patterns, including rivers, streams, and drainage systems, to understand their impact on tunnel construction and design of drainage systems.
- Hydrogeological investigations: Analysis of groundwater conditions, including water table levels, permeability of rock formations, and potential inflow into the tunnel, to design effective dewatering systems and waterproofing measures.

4. Environmental Impact Assessments:

- Ecological surveys: Assessment of the flora, fauna, and habitats in the project area to identify sensitive or protected species and design appropriate mitigation measures.
- Air quality and noise assessments: Evaluation of potential impacts on air quality and noise levels during construction and operation to develop measures for minimizing environmental disturbance.

5. Seismic Risk Assessments:

- Seismic hazard analysis: Evaluation of the seismicity in the region and the potential for earthquakes to assess the design parameters and seismic safety requirements for the tunnel.
- Site-specific seismic studies: Detailed investigation of local seismic conditions, including soil liquefaction potential and ground response analysis, to ensure the tunnel's structural integrity during seismic events.

6. Utility Surveys:

- Utility mapping: Identification and mapping of existing underground utilities, such as water pipelines, gas lines, and electrical cables, to avoid conflicts and plan for necessary relocations.


These surveys and investigations are conducted by a multidisciplinary team of geologists, geotechnical engineers, hydrologists, environmental scientists, and other relevant experts. The data collected from these studies would inform the design and construction methodologies, ensuring the safe and efficient construction of the Khambataki Twin Tunnel.

Design of Tunnel

The design of the new Khambataki Twin Tunnel would involve a comprehensive approach that takes into account various factors such as geological conditions, traffic requirements, safety considerations, and environmental impacts. While the specific design methods can vary depending on project-specific requirements, here are some commonly used methods in the design of tunnels:

Design Considerations:

- Alignment and Geometric Design
- Geotechnical Investigation and Ground Conditions
- Structural Design and Durability
- Ventilation and Air Quality Management
- Fire Safety and Emergency Preparedness



Tunnel alignment and cross-section design

The general direction of Twin Tube Tunnels is North-South, and the twin tubes are termed East Tube and West Tube. Each tube accommodates three lanes one way traffic with a carriageway width of 10.50 m, paved shoulder 2 m width left of slow lane and edge distance of 0.6 m right of fast lane. Crash barrier on fast lane side and kerb on slow lane side are proposed. Foot paths are proposed on both sides of crash barrier / kerb. Drain and Service duct are accommodated below the footpaths. The overall internal width of the tubes is 16.159 m (max.) in general. Emergency lay bye is 100m long x 3.0m and overall width of tunnel at the location is 17.52 m. The lay-bye is provided at mid length of tunnel. The vertical clearance inside of tunnel to crown above carriage way is 9.31 m and provides the minimum vertical vehicle clearance of 5.5 m. SOS niches 1.5m (W) x 2.4m (H) x 2.175m Deep are provided at 200m c/c in left wall of tubes. Concrete pavement is provided for the carriageway. One side cross fall of 2.0% (crash barrier to kerb) is provided in the carriageway. The length of each tube is 1148 m. Waterproofing membrane, 2 mm thick with geotextile layer is provided in between initial support system of shotcrete and final concrete lining to prevent seepage. Central longitudinal drain of 600mm dia. is provided to drain off the ground water seepage from behind water proof membrane. Single lane Cross passage tunnels are provided with 3.5m carriage way with 1m edge strip on both sides, at 287m spacing, for diverting traffic from each tube, in case of emergency. Crash barriers with footpaths are provided on both sides. The overall width of cross passage is 8.5m and vertical clearance at crown is 6.74m.

Construction of Khambataki Twin Tunnel

Tunnelling operations involve certain basic procedures: investigation, excavation and materials transport, ground support, and environmental control. In tunnels, geologic conditions play the dominant role in governing the acceptability of construction methods and the practicality of different designs. Thorough geologic analysis is essential in order to assess the relative risks of different locations and to reduce the uncertainties of ground and water conditions at the location chosen. In addition to soil and rock types, key factors include the initial defects controlling behaviour of the rock mass; size of rock block between joints; weak beds and zones, including faults, shear zones, and altered areas weakened by weathering or thermal action; groundwater, including flow pattern and pressure; plus, several special hazards, such as heat, gas, and earthquake risk. For geological investigation of this twin tunnel bore holes method has been used.



1. Tunnel Alignment:

Geotechnical investigations: Detailed geological studies and site investigations to understand the ground conditions, identify potential hazards, and determine the optimal tunnel alignment.

Geometric design: Consideration of factors such as topography, existing infrastructure, and right-of-way constraints to determine the most suitable alignment for the tunnel.

2. Cross-Sectional Design:

Tunnel dimensions: Determination of the required tunnel dimensions, including the width, height, and shape of the tunnel based on traffic requirements, ventilation needs, and safety considerations.

Structural design: Selection of appropriate tunnel lining materials, such as reinforced concrete segments or shotcrete, and the design of support systems to ensure stability and structural integrity.

3. Excavation of New Khambataki Twin Tunnel:

In this tunnel, partial face blasting i.e., heading and bench method was adopted in which top part of the tunnel which is known as head is blasted first at full width, followed by blasting of the remaining bench. The bench can be excavated later using horizontal or vertical holes depending upon the site conditions. Excavation for this tunnel was cyclic, as by drilling and blasting methods. Here each cycle involves drilling, load explosive, blasting, ventilating fumes, and excavation of the blasted rock (called mucking). Drilling pattern ensures the distribution of explosive in rocks and desired blasting results. Factors taken into consideration while designing drilling patterns are rock drill ability and blast ability, the type of explosive, and blast vibrations restrictions. For drilling cut hole method was used. Cut holes of diameter 45mm and length 4m are drilled in inclination of 30-45 degrees on the bottom most centre of the proposed tunnel face, this is done to provide enough expansion space for the remaining blasted rock around it. After drilling the holes throughout the proposed tunnel face the explosive are loaded.




While loading explosives in drilled holes, sand filling is done up to certain length which is known as stemming. This is done to create high pressure for explosive to blast. In tunnel Excavation, blasting works outwards from the first hole around the uncharged holes in the cut. Each blast provides more space for the following ring of blast holes. For blast design, powder factor is calculated. The powder factor is a relationship between how much rock is broken and how much explosive is used to break it. Powder factor is expressed as explosive quantity per unit volume of blasted rock and

is assumed in the initial stages of construction. The powder factor varies between 0.6 and 5 kg/m³. The correct design of a blast starts with the very first hole to be detonated. In the case of a tunnel blast, the first requirement is to create a void into which rock broken by the blast can expand. This involves drilling a pattern of carefully spaced parallel holes which are then charged with powerful explosive and detonated sequentially using millisecond delays. Once a void has been created for the full length of the intended blast depth or 'pull', the next step is to break the rock progressively into this void. This is generally achieved by sequentially detonating carefully spaced parallel holes, using one-half second delays. The purpose of using such long delays is to ensure that the rock broken by each successive blast hole has sufficient time to detach from the surrounding rock and to be ejected into the tunnel, leaving the necessary void into which the next blast will break. A final step is to use a smooth blast in which lightly charged perimeter holes are detonated simultaneously in order to peel off the remaining half to one metre of rock, leaving a clean excavation surface. Therefore, the periphery holes which are top most holes and floor holes or bottom holes are the last one to be blasted. After cut holes, production holes are blasted in the sequences. All holes are drilled very close to each other and detonated each with its own detonation number. Detonation number decides their sequence of blasting

4. Rock Support and Reinforcement:

- Rock bolts: Installation of steel bolts or anchors into the rock to provide additional support and prevent rockfall.
- Shotcrete: Application of sprayed concrete onto the excavated rock surfaces to stabilize the tunnel walls and provide immediate support.
- Steel ribs: Installation of steel ribs or lattice girders along the tunnel walls to enhance structural stability.



5. Cross passages

Cross passages are constructed in tunnels to provide emergency access and egress between the parallel tunnels & to provide a safe and quick evacuation route for passengers and workers in the event of an emergency.

In the case of the Khambataki twin tunnel, there are two cross passages, spaced 350 meters apart and 400 meters from the start and end of tunnel. These are equipped with emergency communication systems, lighting, and ventilation & they were constructed using the NATM method.



6. Tunnel Portal

The Khambataki twin tunnel have two portals: one at the north end and one at the south end. The north portal is located near Adoshi village and the south portal is located near Khandala.

These portals serve as the entry and exit points for the tunnel, and they are usually located at the ends of the tunnel or at points where the tunnel intersects with the surface.

The portals are typically designed to provide safe and efficient access to the tunnel for both workers and vehicles. They are often constructed using reinforced concrete, with large openings to accommodate the width and height of vehicles that will be using the tunnel.

In addition to providing access, these portals have also included ventilation systems to provide fresh air to the tunnel, lighting to improve visibility, and other safety features such as fire suppression systems and emergency exits.

These Portals in all respects including permanent supports with steel ribs, lattice girders, shotcreting, precast RCC lagging slabs, drilling vertical holes and pre-consolidation grouting with cement slurry etc.

On completion of works for this tunnel portal faces in all respects including appropriate anchors, steel wire weld mesh fabric and shotcreting.



1) 7.False portal in tunnels

It is designed to appear as a real entrance to the tunnel, but is not actually used for entry or exit. False portals are often used for several purposes, including:

- i. Ventilation: False portals can be used to provide ventilation for the tunnel by allowing fresh air to enter and stale air to exit.
- ii. Security: False portals can be used to deceive potential intruders or to mislead attackers in case of an attack on the tunnel.
- iii. Aesthetics: False portals can be used to conceal the appearance of the tunnel and blend it into the surrounding landscape or urban environment.
- iv. Fire safety: False portals can be used to provide a means of escape in case of a fire in the tunnel. In such a scenario, the false portal can be used as an emergency exit.

There are no false portals constructed in the Khambataki twin tunnel yet. But are going to be constructed



to blend in with the surrounding landscape and architecture & due to the height of mountain at the entry and exit.

2) 8. Tunnel Lining

As the tunnel is excavated, various support systems are put in place to prevent collapse and ensure safety. The pre-construction design of initial support system has been worked out based on the rock mass classification parameters. Initial support system includes provision of spilling, steel sets, rock bolts, plain and fibre reinforced shotcrete.



It is proposed to use shotcrete of M30 grade as final lining over a waterproof membrane. This is over and above the primary reinforced shotcrete and rock bolts. The initial sprayed concrete layer did not have any structural role but acted as a barrier to protect the exposed rock against alteration by air and water immediately after the excavation. Hence the final shotcrete layer. The (new) proposed 200 mm thick final sprayed concrete lining (in lieu of the cast in-place concrete) will be applied in layers and can be grooved. Its structure is designed to resist normal forces and bending moments.



9. Drainage Systems:

Drainage design: Implementation of a drainage system to manage water infiltration, prevent flooding, and maintain the stability of the tunnel structure.

Sump pumps: Installation of pumps to remove accumulated water from the tunnel and keep it dry.

In order to trap rainwater from hill slopes and prevent it from flowing into the approach cuts and the tunnels, catch water drains are proposed above the top of sides of approach cuts and above excavated portals in compliance with Cl.9.5 of SP 99-2013.

3) 10. Pavement

Rigid pavement for main carriageway IRC:SP:87-2013 for six laning manual, the black topped road surface inside tunnel, generally constructed on rocky subgrade, gets damaged due to seepage water and creates severe problems for surface drainage. Hence the pavement inside the tunnel and in approach cuts shall be high performance pavement concrete. Further, the project highway requires about 1 km viaduct on Pune side. The project highway on Satara side having rocky strata at shallow depth and requires cutting varies from 3 – 40 m before actual start of the tunnel. Based on the above and considering rocky sub grade from the start of the project to end of the tunnel and viaduct portion, rigid pavement is found advantageous over the flexible pavement. Hence, rigid pavement is recommended for the entire length of the Project Highway. Rigid pavement shall be designed for a design period of 30 years. The stage construction shall not be permitted.

Table 3 - Pavement Composition

Grades	PQC - M40 - 280 mm	DLC - M10 - 150mm	GSB - 150mm
Dowel bar	Diameter - 36mm	Length - 500mm	Spacing - 300m
Tie Bar	Diameter - 12mm	Length - 580mm	Spacing - 400mm

11. Ventilation and Lighting:

Ventilation system design: Determination of ventilation requirements to ensure adequate air quality and control of dust, fumes, and gases within the tunnel.

Lighting design: Placement and selection of lighting fixtures to provide sufficient illumination for safe navigation within the tunnel.

The source for Tunnel illumination is CIE 88:2004 Guide for the lighting of Road Tunnels and Underpasses.

The basic objective of tunnel lighting is to ensure that traffic both during day and night times can approach, pass through and leave the tunnel at the designated speed with adequate safety and comfort not less than that of expressway section before and after the tunnel. The lighting in tunnels, especially during day time, poses number of technical and financial problems. On bright sunlit days, a great difference in luminance level exists between exterior and interior luminance which seriously impairs the visual performance of drivers in adaptation of such abrupt light changes and may lead to hazardous situations.

In other words, the design of lighting at entrance zone of tunnel should be given more attention than at exit zone.

4) *Tunnel Ambiance Monitoring and Ventilation Control and Optimization-*

- i. Carbon Monoxide (CO) cum opacity Sensors will be installed at three locations in each tube. Measured values of CO & opacity will be independently displayed in the GCC (GNU Compiler Collection). Whenever the level of Toxic gas / Opacity rises beyond the pre-set limit value, audio-visual alarm to be activated. Sensors are to be provided at 3 locations in each tunnel. The sensors should have capacity to measure over a linear distance of 10 m. The principle of operation is transmissiometry.
- ii. Linear Temperature Detector: Tunnel temperature to be monitored using Linear Temperature monitoring system duly segmented for operational requirement. Continuous wire will run longitudinally along the tunnel length. The sensor will be segmented in numbers of zones so that discontinuity in one zone would not affect other zones. Measured values of temperature will be independently displayed in the GCC. Whenever the level of temperature rises beyond the pre-set limit value, audio-visual alarm to be activated.
- iii. Air Flow Sensors will be installed in three different places in each tube to indicate flow speed & direction. The operation of Jet fans will be controlled as per the air flow speed & direction. The air flow sensors should operate by ultrasonic method. The transmitter & receivers would be mounted in opposite walls of the tunnels. The output should be 4-20 mA & the sensors should be 'Supervisory control and Data Acquisition (SCADA)' compatible.
- iv. Air switches mounted along the fans will provide positive indication of the fan status.

12. Equipments Used

The construction of the Khambataki twin tunnels involved the use of a wide range of equipment and machinery. Here are some of the major equipment and machinery used in the construction of the tunnels:

- i. Loaders and Dump Trucks

Loaders and dump trucks were used to transport excavated material out of the tunnel and bring in supplies and equipment.



- ii. Concrete Spraying Machines

These machines were used to spray shotcrete onto the tunnel walls to provide structural support.

Lifting Equipment

Cranes and other lifting equipment were used to move heavy equipment and materials in and out of the tunnel.



iii. Safety Equipment

Personal protective equipment such as hard hats, safety glasses, respirators, and hearing protection were used to ensure the safety of workers.

Overall, the equipment and machinery used in the construction of the Khambatki twin tunnels were carefully selected to ensure efficiency, safety, and quality in the excavation and support of the tunnels.

Environmental factors considered during construction of New Khambataki Twin Tunnel

During the construction of a twin tunnel, several environmental factors should be considered to minimize the impact on the surrounding ecosystem. These factors include:

- Mitigation measures: Integration of environmental mitigation measures, such as noise barriers, wildlife crossings, and erosion control measures, to minimize the project's impact on the surrounding ecosystem.
- Sustainable design practices: Incorporation of energy-efficient lighting, renewable energy sources, and environmentally friendly construction materials to reduce the tunnel's carbon footprint.

These design methods are applied through a collaborative effort involving geotechnical engineers, structural engineers, tunneling experts, and other relevant professionals to ensure a safe, efficient, and environmentally conscious design for the new Khambataki Twin Tunnel.

1. Air pollution: Construction activities can contribute to air pollution through the operation of heavy machinery, generating dust and emissions. The implementation of dust control measures, the use of clean-burning equipment, and the proper management of construction materials can help reduce air pollution.
2. Noise pollution: The construction of twin tunnels can generate significant noise levels, which can have adverse effects on nearby communities and wildlife. To mitigate noise pollution, construction companies can use noise barriers, implement work schedules that minimize noise during sensitive periods, and utilize quieter equipment.
3. Water pollution: Construction activities may lead to the runoff of sediment, chemicals, and other pollutants into nearby water bodies. These pollutants can have detrimental effects on water quality and aquatic life. Implementing erosion control measures, managing stormwater runoff, and adopting proper waste management practices can help prevent water pollution.
4. Habitat disruption and biodiversity loss: The construction process can result in the destruction or alteration of natural habitats, displacing and potentially harming local flora and fauna. Conducting thorough environmental impact assessments, minimizing land disturbance, and implementing habitat restoration measures can help mitigate habitat disruption and preserve biodiversity.
5. Soil erosion: Excavation and earthmoving activities during tunnel construction can accelerate soil erosion if not properly managed. Techniques such as slope stabilization, erosion control measures, and the implementation of sedimentation ponds can help reduce soil erosion and sedimentation in nearby water bodies.
6. Cultural heritage preservation: Twin tunnel construction may intersect or impact areas of cultural, archaeological, or historical importance. Careful consideration should be given to assessing and mitigating potential impacts on cultural heritage sites by conducting surveys, archaeological excavations if necessary, and implementing appropriate preservation measures.
7. Energy and resource conservation: Efforts should be made to optimize energy consumption and reduce resource utilization during construction. This can be achieved by implementing efficient construction practices, using eco-friendly materials, promoting recycling and reusing of construction waste, and minimizing the carbon footprint of the project.

By considering these environmental factors and implementing appropriate mitigation measures, construction companies can minimize the negative environmental impacts during the construction of twin tunnels and ensure sustainable development. Additionally, engaging with local communities and stakeholders, and complying with relevant environmental regulations, can contribute to environmentally responsible construction practices.

12. Conclusion & results

This research paper serves as an example of the structure and content that could be included in a study on the construction of twin tunnels.

This research paper provides an in-depth analysis of road safety and road safety audits. It explores the various aspects of road safety, the importance of road safety audits, their methodologies, effectiveness, challenges, and future directions. By highlighting the significance of road safety audits in improving road infrastructure and reducing accidents, this paper aims to contribute to the ongoing efforts to create safer and more sustainable transportation systems.

This research paper gives an extensive analysis of the design considerations involved in the construction of twin tunnels. The paper explored the unique challenges and complexities associated with designing twin tunnels, including alignment, cross-passages, ventilation, and ground support systems. It examined different design approaches, methodologies, and innovative solutions used in twin tunnel projects from around the world. Furthermore, the paper discussed case studies that illustrate successful implementation of twin tunnel designs. The research aims to provide valuable insights into the design principles and best practices for the construction of twin tunnels.

Best Practices and Lessons Learned in Twin Tunnel Design

- a. Collaboration between designers, engineers, and stakeholders for holistic design solutions
- b. Continuous monitoring and feedback for design optimization
- c. Challenges faced and mitigation strategies employed in twin tunnel design projects

Waterproofing and Drainage Design

- a. Importance of waterproofing and drainage in twin tunnel construction
- b. Design methodologies for preventing water ingress and managing groundwater
- c. Membrane and grouting techniques for waterproofing tunnels
- d. Drainage design to ensure efficient water evacuation

Tunnel Support System Design

- a. Role of ground support systems in twin tunnel construction
- b. Determination of appropriate ground support methods based on geological conditions
- c. Design considerations for rock bolts, shotcrete, steel arches, and yielding support systems
- d. Case studies demonstrating effective tunnel support system designs

Alignment Design

- a. Selection of alignment based on project requirements and geological conditions
- b. Factors influencing alignment design including topography, geotechnical considerations, and urban constraints
- c. Techniques for minimizing curvature and providing adequate sight distances
- d. Case studies highlighting successful alignment design in twin tunnels

Cross-Passage Design

- a. Significance of cross-passages in twin tunnel construction
- b. Design considerations for positioning, spacing, and dimensions of cross-passages
- c. Materials and construction techniques for cross-passages
- d. Case studies showcasing innovative cross-passage design solutions

This research paper provided a comprehensive review of the equipment used in the construction of twin tunnels. The paper explores the significance of employing specialized equipment to ensure safety, productivity, and efficiency throughout the tunneling process. It examined various categories of equipment including tunnel boring machines (TBMs), excavation machinery, ground support equipment, ventilation systems, and monitoring tools. Furthermore, the paper analyzed case studies and best practices that showcase successful implementation of equipment in twin tunnel construction projects. This research aims to provide valuable insights into the selection and effective utilization of equipment for twin tunnel construction.

Excavation Machinery

- a. Importance of excavation machinery in twin tunnel construction
- b. Equipment such as excavators, rock breakers, and diggers used for preliminary excavation
- c. Techniques for controlled blasting, drilling, and mucking
- d. Best practices for excavation machinery operation

Ground Support Equipment

- a. Role of ground support equipment in ensuring tunnel stability and safety
- b. Types of ground support equipment including shotcrete machines, grouting equipment, and rock bolts
- c. Installation methods for ground support systems
- d. Case studies showcasing successful utilization of ground support equipment

Sustainable and Eco-friendly Equipment

- a. Importance of sustainability in twin tunnel construction

- b. Eco-friendly equipment options such as electric-powered machinery and low-emission vehicles
- c. Best practices for reducing environmental impact during construction

Best Practices and Challenges in Equipment Selection and Utilization

- a. Considerations for equipment size, power, and adaptability to project requirements
- b. Maintenance and training programs for seamless equipment operation
- c. Challenges such as limited space, difficult ground conditions, and high-pressure environments
- d. Safety protocols and risk mitigation strategies in equipment operation

Advanced Technologies for Surveying Twin Tunnel Projects

- a. Use of GIS for spatial analysis, data management, and visualization
- b. Integration of real-time monitoring systems for early detection of ground movements

Best Practices and Challenges in Surveying for Twin Tunnel Projects

- a. Collaboration between geotechnical engineers, surveyors, and construction teams
- b. Timely and regular surveying to identify changes in ground conditions
- c. Challenges in data interpretation and accuracy of survey results
- d. Integration of survey data into the design and construction process

REFERENCES

1. Aliakbar Golshani, Mahsa Gharizade Varnusfaderani(2019) **“Innovative design modification during construction of a twin tunnel using real-time field data”** Transportation Geotechnics.
2. Jaeyoung Lee, Konstantinos Kirytopoulos, Amjad Pervez, Helai Huang(2022) **“Understanding drivers’ awareness, habits and intentions inside road tunnels for effective safety policies”** Accident Analysis & Prevention.
3. Jianzhong Chen, Linhai You, Meng Yang, Xiaoxia Wang(2022) **“Traffic safety assessment and prediction under different lighting service states in road tunnels”** Tunnelling and Underground Space Technology.
4. Jill Weekley, John Harrell and Tim McCarthy, **"Developing a road safety review tool to identify design standard and safety deficits on high risk road sections"**, Transport Research Arena.
5. Jurewicz Chris, Rita Excel(2016) **“Application of a crash-prescient hazard appraisal model to organize street wellbeing interest in Australia”** Transportation Research Procedia.
6. Katsushi Miura(2003) **“Design and construction of mountain tunnels in Japan”** Tunnelling and Underground Space Technology.
7. Lunardi Pietro(2016) **“Evolution of design and construction approaches in the field of tunnelling: the results of applying ADECO-RS when constructing large underground works in urban areas”** Procedia Engineering.
8. Md Shariful Islam, Maged Iskander(2021) **“Twin tunnelling induced ground settlements: A review”** Tunnelling and Underground Space Technology.
9. Mehara & Agarwal(2013) **“A Systematic Approach for Formulation of A Road Safety Improvement Program in India”** Research Gate.
10. Minh Ngan Vu & Wout Broerea(2018) **“Structural design model for tunnels in soft soils: From construction stages to the long-term”** Applied Research on Civil Engineering and Environment (ARCEE).
11. Oza Daksbeshkumar B. and Prof. S. M. Damodariya(2014) **"Road Safety Audit for Kapurai - Dabhoi Section of State Highway-11"** Global journal for research analysis.
12. Pariklr Vakichi Ashokbhai and Dr. A.M. Jain(2014), **“Road Safety Audit: An identification of black spots on busy corridor between Narol – Naroda of Ahmedabad City”** International Journal of Engineering Research & Technology (IJERT).
13. Rejivas.V. A Bindhu. B. K Bino I. Koshy(2014) **“Road safety audit at selected black spots in the study stretch i.e., Kaloor, Palarivattom and Edapally”** International Journal of Engineering Research & Technology (IJERT).
14. R.K. Goel(2001) **“Status of tunnelling and underground construction activities and technologies in India”** Tunnelling and Underground Space Technology.
15. Tripodia Antonino, Luca Persiaa, Paola Di Masciob, Maria Vittoria Corazzab, Antonio Musso(2012) **“A Decision Support System for Analysis of Vulnerable Road Users Safety Issues: Results of the SAFERBRAIN Project”** Procedia - Social and Behavioral Sciences.
16. Sophia Vardaki, Fanis Papadimitriou, Pantelis Kopelias(2014) **“Road safety audit on a major freeway: implementing safety improvements”** Research Gate.



17. Xue-tao Wang, Thomas von Schmettow, Xiang-sheng Chen, Chang-qing Xia(2022) **“Prediction of ground settlements induced by twin shield tunnelling in rock and soil – A case study”** Underground Space 7.
18. Yanqun Yang, Yu Wang, Said M. Easa, Xiaobo Yan(2022) **“Risk factors influencing tunnel construction safety: Structural equation model approach”** Heliyon.
19. Yao Hu, Huayang Lei, Gang Zheng, Liang Shi, Tianqi Zhang, Zhichao Shen, Rui Jia(2022) **“Ground movement induced by triple stacked tunnelling with different construction sequences”** Journal of Rock Mechanics and Geotechnical Engineering.
20. Zuliang Zhong, Chao Li, Xinrong Liu, Yifei Fan, Ninghui Lian(2021) **“Analysis of ground surface settlement induced by the construction of mechanized twin tunnels in soil-rock mass mixed ground”** Tunnelling and Underground Space Technology.
21. IS 4756: “Safety code for Tunnelling Work”.
22. IRC:SP:87-2013 “Manual of Specification and Standards for Six Laning of Highways Through Public Private Partnership”
23. IRC SP: 99-2013 “Manual For Expressway”.
24. IRC: SP: 88-2010 "Manual on Road Safety Audit”.
25. CIE 88:2004 “Guide For The Lighting Of Road Tunnels And Underpasses”
26. IRC: 67-2012 "Code of Practice for Road Signs".
27. IRC 35-2012: “Code of Practice for Road Markings”.



Impact Factor: 8.423



INTERNATIONAL JOURNAL OF INNOVATIVE RESEARCH

IN SCIENCE | ENGINEERING | TECHNOLOGY

 9940 572 462  6381 907 438  ijirset@gmail.com



www.ijirset.com

Scan to save the contact details