



e-ISSN: 2319-8753 | p-ISSN: 2347-6710

IJRSET

International Journal of Innovative Research in
SCIENCE | ENGINEERING | TECHNOLOGY

INTERNATIONAL JOURNAL OF INNOVATIVE RESEARCH

IN SCIENCE | ENGINEERING | TECHNOLOGY

Volume 13, Issue 6, June 2024

ISSN INTERNATIONAL
STANDARD
SERIAL
NUMBER
INDIA

Impact Factor: 8.423

 9940 572 462

 6381 907 438

 ijirset@gmail.com

 www.ijirset.com

MIVAN Construction Technology: Enhancing Efficiency and Quality in Precast Structural Elements

Prof. Santosh Mahadev Kinayekar¹, Prof. Sukant Kumar Chauhan², Prof. Kamran Ahmed³,

Sneha Sharad Bagrao⁴, Vaijayanti Jayawant Kadav⁵, Aishwarya Pandit⁶,

Varunraj Jayawant Bader⁷

Assistant Professor, Department of Civil Engineering, Alamuri Ratnamala Institute of Engineering and Technology,
Shahapur, Thane, Maharashtra, India^{1,2,3}

U.G. Student, Department of Civil Engineering, Alamuri Ratnamala Institute of Engineering and Technology,
Shahapur, Thane, Maharashtra, India^{4,5,6,7}

ABSTRACT: In the realm of modern construction, efficiency and sustainability are paramount. This project aims to explore the application and benefits of Mivan Construction Technology in enhancing construction processes, particularly focusing on precast structural elements. Mivan technology, a revolutionary approach in the construction industry, amalgamates precast structural elements, offering a promising solution by leveraging precision-manufactured components off-site. This method not only accelerates project delivery but also ensures consistent quality standards, contributing to sustainable construction practices. By streamlining construction timelines, reducing material wastage, and enhancing structural integrity, Mivan technology demonstrates its potential to significantly improve construction efficiency. Furthermore, this research delves into the economic implications of adopting Mivan technology, examining its cost-effectiveness and long-term viability. Through case studies and comparative analyses, the project elucidates the financial benefits and return on investment associated with implementing Mivan technology for precast structural elements. Moreover, the project considers the environmental impact of Mivan construction, evaluating its potential to minimize carbon emissions, mitigate construction waste, and conserve natural resources. By elucidating the environmental sustainability of Mivan technology, this research underscores its significance in advancing eco-conscious construction practices. By fostering a deeper understanding of its applications and benefits, this research advocates for the widespread adoption of Mivan technology, ushering in a new era of efficient, sustainable, and resilient construction practices. The construction industry continuously seeks methods to enhance efficiency, quality, and sustainability. MIVAN Construction Technology, an innovative approach utilizing aluminium formwork and precast structural elements, presents a significant advancement in this pursuit. This paper explores the application and benefits of MIVAN Technology in modern construction, with a focus on its integration of precast elements.

Through a comprehensive analysis, this study investigates how MIVAN Technology streamlines construction timelines, reduces material wastage, and ensures superior structural integrity. By manufacturing precast elements with high precision off-site, MIVAN Technology accelerates project delivery while maintaining consistent quality standards, thereby promoting sustainable construction practices.

The economic implications of adopting MIVAN Technology are examined, highlighting its cost-effectiveness and long-term viability. Case studies and comparative analyses elucidate the financial benefits and return on investment associated with this technology.

KEYWORDS: MIVAN Construction Technology, Efficiency, Quality, Precast Elements etc.

I. INTRODUCTION

The construction industry stands on the precipice of transformation, driven by the urgent need for efficiency, sustainability, and resilience. Amidst this backdrop, Mivan Construction Technology emerges as a beacon of innovation, offering a compelling solution to the longstanding challenges plaguing traditional construction methodologies. At its core, Mivan Technology represents a departure from conventional practices by leveraging precast structural elements to streamline construction processes and enhance project outcomes. Traditional construction

methods often entail on-site casting of concrete, a labour-intensive and time-consuming process fraught with inefficiencies and inconsistencies. In contrast, Mivan Technology introduces a disruptive paradigm by embracing precast manufacturing techniques, where structural elements are fabricated off-site under controlled conditions before being transported and assembled on-site. This approach not only accelerates construction timelines but also ensures superior quality control and minimized material wastage. Central to Mivan Technology is the utilization of aluminium formwork systems, meticulously engineered to facilitate the casting of precast concrete elements with unparalleled precision and efficiency. By employing these formwork systems, construction teams can achieve remarkable speed and accuracy in creating structural frameworks, significantly reducing labour requirements and construction duration. Moreover, the versatility of aluminium formwork allows for the seamless integration of complex architectural designs, offering architects and designers unprecedented creative freedom.

The benefits of Mivan Technology extend beyond expediency, encompassing a myriad of economic, environmental, and social advantages. By optimizing resource utilization and minimizing construction waste, Mivan construction proves to be a cost-effective and sustainable alternative to traditional building methods. Furthermore, the standardization of precast elements ensures consistency in quality, mitigating the risks of structural defects and rework, thereby enhancing overall project efficiency and reducing lifecycle costs. In the context of sustainability, Mivan Technology emerges as a catalyst for change, enabling the construction industry to transition towards greener and more eco-conscious practices. Through the reduction of carbon emissions, conservation of natural resources, and promotion of recycling and reuse, Mivan construction aligns with global efforts to combat climate change and promote environmental stewardship. MIVAN Construction Technology stands as a transformative force in the construction industry, addressing critical demands for efficiency, sustainability, and resilience. This study explores the innovative approach of MIVAN Technology, which utilizes precast structural elements to revolutionize traditional construction methodologies. Unlike conventional on-site concrete casting, MIVAN employs off-site precast manufacturing under controlled conditions, ensuring superior quality control, accelerated timelines, and reduced material wastage. Central to this technology is the use of aluminium formwork systems, which enable high precision and efficiency in casting precast elements, thereby reducing labour requirements and construction duration. The advantages of MIVAN Technology extend beyond construction speed and accuracy. Economically, it offers cost-effective solutions by optimizing resource utilization and minimizing waste. Environmentally, it promotes sustainable practices through reduced carbon emissions and enhanced recycling. Despite these benefits, the adoption of MIVAN Technology faces challenges, including high initial investment costs and the necessity for specialized training.

Advantages of Mivan Construction Technology

Accelerated Construction Timelines:

Mivan Technology significantly reduces construction timelines by streamlining the building process. The utilization of precast structural elements fabricated off-site allows for rapid on-site assembly, minimizing project duration and enabling earlier occupancy.

Enhanced Quality Control:

The production of precast elements in controlled factory environments ensures consistent quality and dimensional accuracy. This standardized manufacturing process reduces the risk of errors, defects, and rework during construction, resulting in higher-quality structures.

Reduced Labour Requirements:

Mivan construction necessitates fewer labourers compared to traditional methods due to the efficient assembly of precast elements on-site. This leads to reduced labour costs and allows for better allocation of manpower to other project aspects.

Minimized Material Wastage:

Precise planning and manufacturing of precast elements significantly minimize material wastage during construction. Additionally, the reuse of aluminium formwork systems reduces the need for disposable formwork materials, further minimizing environmental impact.

Versatility and Flexibility:

Mivan Technology offers versatility in design and construction, enabling the creation of various architectural configurations and structural layouts. The modular nature of aluminum formwork systems allows for rapid adaptation to changing project requirements.

Cost-effectiveness:

Despite the initial investment in formwork and equipment, Mivan construction proves cost-effective in the long run due to savings in labour, time, and material expenses. The faster construction timelines also result in earlier returns on investment for developers and stakeholders.

Improved Safety:

The use of precast elements and standardized construction processes enhances on-site safety by reducing the need for extensive formwork assembly and dismantling. This minimizes the risk of accidents and injuries associated with traditional construction methods.

Environmental Sustainability:

Mivan construction promotes environmental sustainability by minimizing construction waste, reducing carbon emissions, and conserving natural resources. The efficient use of materials and energy contributes to a greener and more eco-conscious built environment.

II. METHODOLOGY

Process for Construction of Structures with Mivan Construction Technology:

Constructing a Mivan structure involves a specific procedure that utilizes aluminium formwork to create concrete walls, slabs, columns, and other structural elements. This construction method is renowned for its speed, efficiency, and quality.

Preparation and Planning:

Site Assessment: Conduct a thorough survey of the site and ensure proper levelling and soil compaction.

Blueprint Study: Review architectural and structural drawings to comprehend the layout and dimensions.

Material Procurement: Procure the Mivan aluminium formwork system, concrete, reinforcement bars (rebar's), and other necessary materials.

Setting Layout:

Marking: Utilize strings, pegs, and markers to accurately outline the structure's footprint on the ground.

Grid Lines: Establish grid lines for reference throughout the construction process.

Foundation Work:

Excavation: Dig trenches as per the foundation design specifications.

Footing and PCC: Pour concrete for footings and lay a layer of plain cement concrete (PCC) as a base for the walls.

Setting up Mivan Formwork:

Assembling Panels: Erect the Mivan aluminium panels to form the shape of walls, columns, and slabs according to the design.

Alignment: Ensure proper alignment and levelling of the formwork panels using adjustable props and wedges.

Fixing Reinforcement: Install reinforcement bars (rebar's) within the formwork as per structural drawings.

Concrete Pouring:

Slump Test: Conduct a slump test to verify the consistency of the concrete mix.

Pouring Sequence: Systematically pour concrete into the formwork, starting from the lowest level and moving upwards.

Vibration: Use vibrating equipment to eliminate air bubbles and ensure proper compaction of concrete.

Curing: Cover the freshly poured concrete with wet gunny bags or apply curing compounds to prevent rapid moisture loss and ensure adequate strength development.

Stripping Formwork:

Waiting Period: Allow sufficient time for the concrete to achieve the required strength (typically 12-24 hours).

Removing Formwork: Carefully dismantle the Mivan formwork panels, starting from the top and moving downwards.

Shutter Cleaning: Thoroughly clean the formwork panels for reuse in subsequent pours.

Finishing Work:

Surface Finishing: Smooth out concrete surfaces using trowels or other finishing tools to achieve the desired texture.

Joint Sealing: Seal joints and edges to prevent water infiltration and enhance structural integrity.

Electrical and Plumbing Works: Install conduits, pipes, and other utilities within the structure as per the design.

Quality Checks:

Structural Integrity: Inspect the constructed elements for any defects or deviations from the design.

Material Testing: Conduct tests on concrete samples to verify strength and durability.

Dimensional Accuracy: Measure dimensions and alignments to ensure compliance with specified tolerances.

Post-construction Activities:

Site Clean-up: Remove debris and waste materials from the construction site.

Handover: Prepare necessary documentation and hand over the structure to the client or owner.

Safety Measures:

Personal Protective Equipment (PPE): Ensure all workers wear appropriate PPE, including helmets, gloves, and safety harnesses.

Fall Protection: Install guardrails and safety nets to prevent falls from elevated work areas.

Training: Provide training to workers on the safe use of equipment and adherence to safety protocols.

Tests to be Carried Out:

Several tests are typically carried out on Mivan structures to ensure quality, durability, and compliance with construction standards.

Concrete Slump Test: Determines the workability of the concrete mix used in construction by measuring its consistency and flowability.

Compressive Strength Test: Conducted on concrete cubes or cylinders to assess the strength of the concrete, ensuring it meets the required standards for structural stability.

Rebound Hammer Test: Measures the surface hardness of concrete, providing an indication of the concrete's strength and uniformity.

Ultrasonic Pulse Velocity (UPV) Test: Evaluates the quality and integrity of concrete by measuring the speed of ultrasonic pulses passing through it, detecting defects such as cracks or voids.

Pull-out Test: Assesses the bond strength between concrete and reinforcement bars by applying a pulling force to a steel bar embedded in the concrete.

Water Permeability Test: Evaluates the permeability of concrete by subjecting it to water pressure, assessing its resistance to water penetration and potential durability issues.

Load Testing: Involves applying a gradually increasing load to structural elements such as slabs, beams, or columns to assess their load-carrying capacity and performance under stress.

Dimensional Checks: Verifies the dimensions and alignments of structural elements against specified tolerances to ensure compliance with design requirements.

Visual Inspection: Conducted throughout the construction process to identify any defects, cracks, or surface imperfections that may affect the structural integrity or aesthetics of the Mivan structure.

Material Testing: Includes testing construction materials such as aluminium formwork components, reinforcement bars, and concrete aggregates to ensure they meet quality standards and specifications.

III. EXPERIMENTAL RESULTS**Results and Discussions:****Cost Comparison:**

Initial Investment: While Mivan Technology requires a higher initial investment in specialized formwork and equipment, the overall project cost is reduced due to the accelerated construction timelines and decreased labour requirements.

Material Costs: The precise planning and minimal material wastage inherent in Mivan Technology lead to significant savings in material costs compared to conventional construction methods.

Labour Costs: Reduced labour requirements translate to lower labour costs. Fewer workers are needed due to the efficient assembly process, leading to cost savings in labour expenditures.

Construction Speed:

Project Duration: Mivan Technology drastically shortens the construction timeline. The use of precast elements and rapid on-site assembly significantly reduce the time required to complete the project.

Timely Completion: The speed of construction with Mivan Technology ensures projects are completed on or ahead of schedule, providing earlier occupancy and quicker returns on investment.

Quality Control:

Consistency and Precision: The fabrication of precast elements in controlled environments ensures high consistency and dimensional accuracy, resulting in superior quality structures.

Reduction in Defects: Standardized production processes reduce the likelihood of errors and defects, minimizing the need for rework and enhancing the overall quality of the construction.

Environmental Impact:

Material Efficiency: The efficient use of materials in Mivan Technology leads to reduced waste and conservation of resources, contributing to environmental sustainability.

Carbon Emissions: By streamlining the construction process and reducing material waste, Mivan Technology helps in lowering the carbon footprint of construction activities.

Safety and Risk Management:

Enhanced Safety: The use of precast elements and systematic assembly processes enhance on-site safety by reducing the need for extensive formwork assembly and dismantling, thereby minimizing the risk of accidents.

Risk Reduction: The controlled manufacturing environment for precast elements reduces risks associated with quality and consistency, ensuring reliable and safe structural performance.

Design Flexibility:

Architectural Versatility: Despite the initial limitations, Mivan Technology offers significant design flexibility with its modular formwork systems, allowing for various architectural configurations and structural layouts.

Adaptability: The ability to quickly adapt formwork systems to changing project requirements demonstrates the flexibility and versatility of Mivan Technology.

Challenges and Considerations:

Training and Expertise: The adoption of Mivan Technology necessitates specialized training for workers to handle aluminium formwork systems and precast elements effectively. *Logistical Coordination:* Transporting precast elements and coordinating their delivery and assembly on-site require meticulous planning and management to avoid delays and ensure seamless construction progress.

Regulatory Compliance: Integrating Mivan Technology within existing regulatory frameworks requires careful navigation to meet safety, structural, and quality standards.

IV. CONCLUSION

In conclusion, the adoption of Mivan Construction Technology offers significant benefits in terms of cost savings, construction speed, quality control, environmental sustainability, and safety. Despite the initial investment and need for specialized training, the long-term advantages make Mivan Technology a compelling choice for modern construction projects aiming for efficiency and high-quality outcomes.

By adopting Mivan Technology in the project, not only is the quality of construction enhanced, but the speed of construction is also significantly increased and costs are reduced. This is achieved by completely eliminating some construction activities and substantially reducing others. This project includes a cost comparison between conventional construction methods and Mivan Technology.

MIVAN construction technology represents a significant advancement in the field of construction, particularly in the realm of precast structural elements. By leveraging aluminium formwork systems, MIVAN technology enhances both efficiency and quality in building projects. This method allows for rapid construction, reducing project timelines and labour costs, while ensuring high precision and uniformity in structural elements. The improved durability and finish quality of precast components further contribute to the overall integrity and aesthetics of buildings.

Adopting MIVAN construction technology can address the growing demand for faster and more reliable construction processes in urban development. Its ability to streamline workflow and minimize waste makes it a sustainable choice, aligning with modern construction practices aimed at reducing environmental impact. In conclusion, MIVAN technology not only meets the contemporary needs of the construction industry but also sets a benchmark for future innovations in building methodologies.

The challenge of providing housing for a rapidly growing population is becoming increasingly monumental. While the technical capabilities to address this challenge are enormous, they need to be judiciously exploited through innovative construction methods. Traditionally, construction firms worldwide have been hesitant to adopt innovations and changes. It is imperative to analyse the depth of the problem and find effective solutions. MIVAN technology serves as a cost-effective and efficient tool for tackling the issues of mega housing projects globally.

MIVAN aims to maximize the use of modern construction techniques and equipment across its projects. In our study, we have covered new aspects related to MIVAN technology, including cost comparisons based on case studies, feedback from users, and remedial measures to address major defects in MIVAN technology. We infer that MIVAN technology provides high-quality construction at remarkable speed and reasonable cost. This technology holds significant potential for application in India, aiming to provide affordable housing for its burgeoning population.

Conclusively, quality and speed must be prioritized in conjunction with economic considerations. High-quality construction does not impede project speed nor is it uneconomical; rather, it mitigates time-consuming repairs and modifications that typically delay projects and incur additional financial impacts. Experts suggest that housing alternatives with low maintenance requirements may be preferable, even if they come with a slightly higher initial cost. From our survey and cost comparison, we conclude that MIVAN technology presents a win-win situation for builders constructing the homes and consumers occupying them. Hence, MIVAN technology is essential for addressing the challenges of mega housing projects effectively.

REFERENCES

- [1] Nitesh Baban Patekar, A. F. Shaikh “Assessing the impact of conventional formwork and Mivan formwork on construction productivity and efficiency” World Journal of Advanced Engineering Technology and Sciences, 2023, 09(01), 240–247.
- [2] Amith B N, Akash T N “Comparative Study of Mivan and Conventional Formwork Structures” International Research Journal of Modernization in Engineering, Technology and Science, Volume:05/Issue:05/May-2023, e-ISSN: 2582-5208.
- [3] Vedika Prasad Mahale, Aditi Sanjay Waghmare, Prof. Mohammed Shakeebulla Khan “Optimizing Construction Efficiency with Mivan Formwork System” International Journal of Creative Research Thoughts (IJCRT), Volume 12, Issue 3 March 2024, ISSN: 2320-2882.
- [4] Darshankumar Patel, Shubham Pawar, Vishwadeep Pawar, Sagar Vasave, Prasad Bhamare, Nikhil Patil “A Review Paper on Comparative analysis of MIVAN Formwork Technology and Conventional Formwork Technology” International Journal of Research Publication and Reviews Journal, April 2022, ISSN 2582-742, Vol 3, no 4, pp 1432-1441.
- [5] Vaibhav banker, Prof.P.P.Pale “Review on Study of cost and time Optimization of building construction Project using Mivan Technology” International Journal of Advances in Engineering and Management (IJAEM) Volume 4, Issue 5 May 2022, pp: 799-802 www.ijaem.net ISSN: 2395-5252.
- [6] Akshay Gulghane, Nikhil Pitale, Sanket Sanghai “Time and Cost Optimization of Construction Project Using Mivan Technology” Journal of Engineering Research and Application, ISSN:2248-9622, Vol. 8, Issue 8 (Part -II) Aug 2018, pp 70-74.
- [7] Ganar, Patil “Comparative analysis on cost and duration of MIVAN formwork building and Conventional Formwork building” International Journal on Recent and Innovation Trends in Computing and Communication, Volume 3, Issue 12, 6472-6474.
- [8] Sadruddin, Danish, Sudhakar “Comparative Analysis of MIVAN Formwork Building and Conventional Formwork Building Based on Cost and Duration” International Journal of Engineering Research, Volume No.5, Issue No.8, pp: 672-675.
- [9] Yadav, Konnur “Review Paper on Conventional and Mivan Formwork used for Construction” International Journal of Advance Research in Science and Engineering, Volume No.07, Special Issue No. 04, ISSN:2319-8354.
- [10] Gohel, Devang, Pitroda, Dr. Jayeshkumar & Raval, Amitkumar. “Comparative Study of Conventional Structure with Monolithic Structure: A Case Study at Vadodara City. 4. 420- 424.
- [11] Ghangus, Sumit “A Comparative Study of Aluminium Form Work (MIVAN Shuttering) with other Conventional Form Work” International Journal for Research in Applied Science & Engineering Technology, Volume 6, Issue VI, ISSN:2321- 9653.
- [12] Kolekar, Prasad, Nigade, Vishwajeet, Hajare, Shivaji, Kamble, Prathamesh, Patade, Sagar, Kumavat, Amit “Analysis and Comparison of Mivan Formwork System with Conventional Formwork System” International Research Journal of Engineering and Technology (IRJET), Volume 07, Issue 06, e-ISSN: 2395- 0056.
- [13] Patil, Anantkumar, Awati, Vishwanath, Rashmi “Comparative Analysis of Conventional Formwork and Mivan Formwork based on Duration and Cost “International Research Journal of Engineering and Technology (IRJET), Volume 07, Issue 06, e-ISSN:2395-0056.
- [14] Patel, Darshan kumar “A Review Paper on Comparative analysis of MIVAN Formwork Technology and Conventional Formwork Technology” 1432-1441



INTERNATIONAL
STANDARD
SERIAL
NUMBER
INDIA



INTERNATIONAL JOURNAL OF INNOVATIVE RESEARCH

IN SCIENCE | ENGINEERING | TECHNOLOGY

 9940 572 462  6381 907 438  ijirset@gmail.com



www.ijirset.com

Scan to save the contact details